TP332

Project

Caversham House Caversham Berkshire





Contractors / Partners





TP332

Project

Caversham House Caversham Berkshire



Project Brief

In consultation with Elegant Homes Reading Ltd, Thermotec were asked to provide a complete design and installation scheme, in compliance with the latest environmental and technological heating systems.

Scope of Works

Thermotec delivered a fully integrated floor build up system from the sub-floor base to the final floor screed using our TPA11 Aquafloor warm water Underfloor Heating for all the apartments. The project was managed, installed and supervised by Thermotec, and was delivered on time and within budget.




Project Details

Elegant Homes Reading Ltd have created four duplex apartments in the stunning Caversham House. With accommodation stretching over two floors providing flexible living space presented to a high standard.

890 m2







Aquafloor Installation

- Expansion edging strip Screed minimum 65mm Aquafloor heating pipe Heating pipe rail Foil faced insulation min 25mm Solid sub-floor
- 6





Unsurpassed in logistics and project planning. Assured quality installations for the mechanical and electric sector.

thermotecuk.com